

LSC Kingwood Fire Science — Water Line & Septic System

CSP 26-08-10 | Materials/quantity breakdown for human estimator review | Report-only, no bid submitted

Report-only. This is a materials/quantity breakdown generated from the real bid attachments for internal review. It does not submit a bid, price a proposal, or commit ENGCO to anything — every line is either cited to an exact source or explicitly flagged as needing human takeoff.

22	18	4
total line items	cited/verified	flagged for human takeoff

Div	Item	Qty	Unit	Confidence	Source
33	Kingwood Drive segment, 12-inch C900 PVC (STA 1+00.00 to STA 6+00.00, tie-in to wet connection) No bid-quantity sheet exists in this set and no single station is printed as "end of line," but the sheet's own survey curve data gives an exact length by arithmetic, not a guess: 59.83 ft (STA 1+00 to PC) + 299.25 ft (curve arc, PC to PT) + 140.89 ft (tangent past PT, per the printed bearing+distance call) = 499.97 LF. Cross-checked a second way, by straight station subtraction (end STA 6+00.00 [=PT 4+59.07 + 140.89] minus begin STA 1+00.00) = 499.96 LF. The two independent computations agree to within 0.01 ft — real closure, not rounding luck. Also visually confirmed against the rendered plan sheet (not just trusted from text): the 'PROP 12" PVC (C-900) WATER LINE (PUBLIC)' leader points directly at the dashed line that sweeps through this exact curve, and that same line runs unbroken through the tangent to the '1 - 12" WET CONNECTION' callout at the far end — the hydrant labeled 'STA 4+59' sits exactly where the curve visually straightens, matching the printed PT: 4+59.07. This whole segment is 12-inch pipe only; no 8-inch is called out on this sheet (Sorters Rd is where the 12-to-8 transition happens, on the next line).	499.96	lf	cross_checked	26 0813 - LSC Kingwood FTF_Aproved PUB Plans_260813.pdf p4 — STA. 1+00.00 KINGWOOD DRIVE (baseline origin); PC: 1+59.83; L=299.25 R=2150.000 T=149.865 (curve data); PT: 4+59.07; tangent-out bearing N88°13'09.99"E, distance 140.89 (all printed directly on the plan-and-profile sheet)
33	Sorters Road segment, 12-inch/8-inch C900 PVC (STA 1+00.00 to STA 4+13.47, tie-in to trenchless crossing) 313.47 LF = 413.47 - 100.00, station arithmetic between two independently, explicitly printed station callouts (both sheets agree on the tie-in station exactly). This is the one segment length on this project defensible enough to call cross_checked rather than a plan-scaled estimate. Includes the 12-inch-to-8-inch transition; sheet 05's profile shows the transition graphically but does not print its exact station.	313.47	lf	cross_checked	26 0813 - LSC Kingwood FTF_Aproved PUB Plans_260813.pdf p5 — STA. 1+00.00 SORTERS ROAD (baseline origin, shared with Kingwood Drive STA 1+00.00) 26 0813 - LSC Kingwood FTF_Aproved PUB Plans_260813.pdf p6 — STA. 4+13.47 SORTERS ROAD = STA. 1+34.68 SORTERS ROAD CROSSING (explicit tie-in station, printed on both sheet 05 and sheet 06)
33	Trenchless 8-inch C900 PVC crossing under Sorters Road Real independent agreement: the SOW's 'approximately 44 linear feet' and the plan's printed '44 LF' label match exactly.	44	lf	cross_checked	26 0814 SOW Water Line 12 & 8 RV1.pdf p4 — Construct approximately 44 linear feet of trenchless 8-inch C900 PVC public water line crossing Sorters Road... 26 0813 - LSC Kingwood FTF_Aproved PUB Plans_260813.pdf p6 — PROP. 44 LF TRENCHLESS CONSTRUCTION (PUBLIC) — printed directly on the Sorters Road Crossing plan-and-profile sheet

Div	Item	Qty	Unit	Confidence	Source
33	Ductile iron pipe transition sections (AWWA C151, C104 lining, 8-mil poly wrap) Real requirement, shown graphically (hatched) on sheets 04-06 profiles at each vertical-bend/casing location, but no length is labeled at any transition. Needs a human take-off from the profile details.	—	lf	unresolved	26 0814 SOW Water Line 12 & 8 RV1.pdf p4 — <i>Provide required transitions between PVC and ductile iron pipe and fittings...</i>
33	12-inch wet connection to existing City water line	1	ea	cross_checked	26 0814 SOW Water Line 12 & 8 RV1.pdf p4 — <i>Perform one 12-inch wet connection to the existing 12-inch City water line on Kingwood Drive...</i> 26 0813 - LSC Kingwood FTF_Aproved PUB Plans_260813.pdf p4 — <i>1 - 12" WET CONNECTION / REMOVE EXIST. PLUG AND BOV AND CONNECT PROP. 12" WATER LINE TO EXIST. 12" WATER LINE — printed callout, east end of Kingwood Drive sheet</i>
33	Fire hydrant assemblies (6-inch lead, auxiliary valve, thrust restraint) Counted from the plan-view fire-hydrant symbol + station callout on each sheet, not from a schedule table (none exists on this set) — flagged vision_count, not schedule_verified. A human should re-confirm against the full-size plan before pricing.	4	ea	vision_count	26 0813 - LSC Kingwood FTF_Aproved PUB Plans_260813.pdf p4 — <i>Counted 4 fire-hydrant symbols with F.H. callouts across sheets 04-06: STA 1+44 (Kingwood Dr), STA 4+59 (Kingwood Dr), Sorters Rd mid-segment, STA 4+18 (Sorters Rd)</i>
33	Gate valves with box, various sizes (6", 8", 12") at tees/connections Real, plainly labeled on every plan sheet (e.g. '2-12" G.V. W/ BOX', '1-6" G.V. W/ BOX', '1-8" G.V. W/ BOX') at each tee and connection cluster — but several fitting clusters appear on more than one sheet where two sheets share a boundary point (Kingwood Dr/Sorters Rd junction shown on both sheet 04 and sheet 05; Sorters Rd/crossing junction shown on both sheet 05 and sheet 06). Double-counting a shared-boundary cluster is a real risk here — the same failure mode this toolkit already hit and fixed once on Nueces's pier caps. Rather than guess which clusters are duplicates without a clean way to cross-check station coordinates between sheets, this is left for a human to tally directly off the full-size plans (or the source CAD/DWG file, referenced in the plan sheets' title blocks) rather than risk a wrong number with a confident label.	—	ea	unresolved	n/a (unresolved)
33	12-inch fittings: tees, 45° bends, plugs and clamps at line ends/junctions Same shared-boundary double-count risk as the gate valves above — flagged for the same reason, not guessed at.	—	ea	unresolved	n/a (unresolved)
33	8-inch fire-rated compound meter assembly (FRCWMA) with vault, in 31'x15' water meter easement	1	ea	cross_checked	26 0814 SOW Water Line 12 & 8 RV1.pdf p4 — <i>...8-inch fire-rated compound meter with vault (FRCWMA) in the 31'x15' water meter easement...</i> 26 0813 - LSC Kingwood FTF_Aproved PUB Plans_260813.pdf p6 — <i>PROP. FRCWMA W/ VAULT, labeled on the Sorters Road Crossing plan and profile</i>
33	8-inch reduced pressure zone (RPZ) backflow preventer assembly, on private property	1	ea	cross_checked	26 0814 SOW Water Line 12 & 8 RV1.pdf p4 — <i>...and the 8-inch reduced pressure zone (RPZ) backflow preventer assembly located on private property...</i> 26 0813 - LSC Kingwood FTF_Aproved PUB Plans_260813.pdf p6 — <i>PROPOSED 8" REDUCED PRESSURE ZONE (RPZ) BACKFLOW PREVENTOR IN PRIVATE PROPERTY — key note W2, Sorters Road Crossing sheet</i>

Div	Item	Qty	Unit	Confidence	Source
33	System design capacity	272	gpd	schedule_verified	26 0818 SOW Septic System.pdf p1 — <i>The system shall be constructed to accommodate a maximum daily usage of 272 Gallons Per Day (GPD).</i>
33	Minimum required trench bottom area	1,360	sf	schedule_verified	26 0818 SOW Septic System.pdf p1 — <i>The contractor shall prepare a minimum required trench bottom of 1,360 square feet...</i>
33	Engineered drip disposal area	2,560	sf	schedule_verified	26 0818 SOW Septic System.pdf p1 — <i>...and install the engineered drip area across 2,560 square feet.</i>
33	Pretreatment tank, 500-gallon	1	ea	schedule_verified	26 0818 SOW Septic System.pdf p1 — <i>Furnish, excavate, and install a 500-gallon pretreatment tank...</i>
33	Clearstream aerobic treatment unit, 800-gallon	1	ea	schedule_verified	26 0818 SOW Septic System.pdf p1 — <i>...an 800-gallon Clearstream Treatment Unit...</i>
33	Pump tank, 1,080-gallon SOW explicitly states no chlorinator is required — do not price one.	1	ea	schedule_verified	26 0818 SOW Septic System.pdf p1 — <i>...and a 1,080-gallon pump tank. A chlorinator is not required for this specific design.</i>
33	Simplex effluent pump, Goulds 20 EB, 0.5 HP	1	ea	schedule_verified	26 0818 SOW Septic System.pdf p1 — <i>...a Simplex Effluent Pump (Goulds 20 EB 1/2 HP)...</i>
33	Solids pump, 2-inch, Goulds, in dosing tank	1	ea	schedule_verified	26 0818 SOW Septic System.pdf p1 — <i>...a 2-inch Goulds Solids Pump inside the dosing tank...</i>
33	Effluent pump, Goulds, 0.5 HP, 20 GPM	1	ea	schedule_verified	26 0818 SOW Septic System.pdf p1 — <i>...and a 0.5 HP Goulds 20 GPM Effluent Pump.</i>
33	Dual filter, Aztec, 100 micron	1	ea	schedule_verified	26 0818 SOW Septic System.pdf p2 — <i>Install an Aztec Dual 100 Micron Filter to ensure effluent clarity and protect the drip infrastructure.</i>
33	Drip tubing, Netafim, 0.91 GPH, across the 2,560 SF drip field Quantity re-stated from the drip-area line above — this is the area the tubing must cover, not a separate linear-footage figure (none given; drip emitter spacing/lateral spacing needed to convert to LF of tubing is not in the SOW).	2,560	sf	schedule_verified	26 0818 SOW Septic System.pdf p2 — <i>Install Netafim 0.91 GPH drip tubing throughout the designated absorption area.</i>
33	Supply piping, training facility building to septic system (Sch 40 or DWV) No length given in the SOW; the septic system's own 2-page SOW has no site plan showing the building-to-tank distance. Needs the actual site/civil plan for the fire training facility building, which is not included in this bid-attachments package.	—	lf	unresolved	26 0818 SOW Septic System.pdf p1 — <i>Install Schedule 40 or DWV thick-wall pipe for all connections running from the training facility building to the septic system.</i>